



## Space

8,192 Sq Ft (4,903 sq ft non-raised)  
42U APC AR3100 Cabinets



## Connectivity

Carriers Available: Cogent, AT&T,  
LGN

Port Sizes up to 100GE  
Wave Enabled



## Security

Pin Pad Access  
Multiple cameras monitoring the site



## Environment

Fike Cheetah Fire Alarm System with  
safety systems  
VESEDA Xtralis  
Fike Halon Clean Agent Zones  
Suppression Systems  
Multiple HVAC Units



## Power

Three LaMarche Rectifiers – each 200 amps  
Five strings of 170AH DC Batteries  
One 450kW Cummins-Onan generator  
2500 gallon diesel fuel storage tank  
with Veeder Root monitoring unit  
Two 800amp Automatic Transfer Switches

