



Space

39,601 Sq Ft (6,897 sq ft raised; 26,264 sq ft non-raised) 42U APC AR3100 Cabinets Free WiFi



Carriers Available: Cogent, Verizon, Sunesys, Fibertech Port Sizes up to 100GE Wave Enabled



Card Reader Access System Cameras monitoring and recording 24/7 **Gated Facility** 

				•
_	_	_	_	
5	<	5	*	


## Environment

VESDA Xtralis **Clean Agent Zones Suppression Systems Multiple HVAC Chillers Multiple Air Handling Units** 



One 500kVA UPS Unit Two 80kVA UPS Units (expandable to 120kVA) with a string of East Penn AVR95-9 batteries Multiple PDUs for distribution (ranging from 75KVA to 120KVA) Two 1250kW Diesel Powered Standby Generators with 2000amp ATS

See Back for Floor Plan



**First Floor** 

